RIVERWALK

STAGE 33 GEELONG ROAD, WERRIBEE WYNDHAM CITY COUNCIL

FOR




CIVIL DRAWINGS ROADS AND DRAINAGE


DCE REF: 10933RD MELWAY REF: 244 F2

© Dalton Consulting Engineers Pty Ltd









REGRADE LOT AT MIN 1 IN 150 ■ SIGNAGE

PSM | TBM

OVERLAND FLOW

CONCRETE PATH | D'WAY

0 CONSTRUCTION ISSUE

Written dimensions to take precedence over scale. Contractor shall check and verify all dimensions on site. Discrepancies to be brought to the attention of the Superintendent.

REV DESCRIPTION

13/04/22 SR/MM

13/04/22

889339

Date

−Ex S−O− EX. SEWER MAIN & MH

TBM SCHEDULE

I.D.	TYPE	EASTING	NORTHING	LEVEL
243	ROD	292970.124	5800172.240	16.17
247	PM 32	293136.811	5800075.951	22.20
6002	ROD	293152.965	5800132.136	19.94

TBM'S No. 6002 & 247 ARE SHOWN IN DRG. No. 10933SP01. SHEET No. 05.

NOTE: EXISTING SURFACE LEVELS ALL EXISTING SURFACE LEVELS SHOWN ON THIS PLAN ARE PRIOR TO THE COMMENCEMENT OF PERMIT 6 BULK

NOTE: END OF PAVEMENT WORKS CONCRETE EDGE STRIP AND AG DRAIN TO BE INSTALLED TO

NOTE: EXISTING SERVICES

ALL EXISTING SERVICES UNDER NEW AND PROPOSED ROAD PAVEMENT, FOOTPATH AND DRIVEWAYS TO BE FCR

NOTE: EXISTING STRUCTURES

ALL EXISTING DRAINAGE PITS AND SEWER STURCTURES WITHIN NEW WORKS ARE TO BE ADJUSTED TO MATCH NEW FINISHED SURFACE LEVELS.

NOTE: TACTILE PAVING

TACTILE GROUND SURFACE INDICATORS (TGSI'S) ARE SHOWN INDICATIVELY AND SHOULD BE CONSTRUCTED IN ACCORDANCE WITH AS/NZS 1428.4.1:2009.

NOTE: PARKING BAYS

WHERE APPLICABLE PARKING BAYS TO NEATLY MATCH AND TRANSITION INTO CROSSOVERS AS NOMINATED ON DP01-DP03. ALL OTHER PARKING BAYS ARE TO BE CONSTRUCTED IN

BEWARE!

DEVELOPMENT VICTORIA FTTH OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 03 9311 4575.

BEWARE!

NBN OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 1800 687 626.

TELSTRA OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 9253 8263.

CAUTION!

TELSTRA MAJOR CABLES ARE IN THE VICINITY OF WORKS.

DANGER!

OVERHEAD ELECTRICITY TRANSMISSION LINES. CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN OPERATING IN THE VICINITY OF THESE LINES. THE CONTRACTOR MUST ADHERE TO ALL "NO GO ZONE" REQUIREMENTS OF THE POWER AUTHORITY.

WARNING!

NO DRAINAGE WORKS SHALL COMMENCE UNTIL THE CONTRACTOR CONFIRMS THE I.L. OF ALL EXISTING DRAINS, AND CONFIRMS IN WRITING WITH THE ENGINEERING SUPERVISOR.

WARNING!

THE LOCATION OF EXISTING SERVICES SHOWN ON THESE PLANS MUST BE PROVEN ON SITE, THE APPROPRIATE AUTHORITY MUST BE CONTACTED AND THE SERVICES LOCATED PRIOR TO COMMENCEMENT OF ANY WORKS.

WARNING!

BEWARE OF ASBESTOS! SOME UNDERGROUND SERVICES MAY BE CONSTRUCTED FROM ASBESTOS CONTAINING MATERIAL. CONTACT THE SUPERINTENDENT FOR INSTRUCTIONS ON HOW TO MANAGE ANY POTENTIAL ASBESTOS HAZARD.

CONSULTING ABN 78 429 221 049 QUEENSLAND

T 61 7 3374 9000 E info@dceng.com.au

VICTORIA T 61 3 9813 7400 W dceng.com.au

CONSTRUCTION

Scale @ A1/A3

1:500 / 1:1000

Drawing No. 10933DP01 Sheet No. 06 of 52

Rev 0

Designed K.LIM WAN

Checked

Date

Date

13/04/22 SR/MM

DATE AMEND APP'D

0 CONSTRUCTION ISSUE

Written dimensions to take precedence over scale. Contractor shall check and verify all dimensions on site. Discrepancies to be brought to the attention of the Superintendent

REV DESCRIPTION

09/12/20

2861068

22/01/21

972433

Approved T.LIAKOPOULOS

13/04/22

889339

J.HOLLAND

EX. DRAIN & PIT

—Ex S—O— EX. SEWER MAIN & MH

REGRADE LOT AT MIN 1 IN 150 ■ SIGNAGE

OVERLAND FLOW

TABLE OF SERVICE LOCATIONS

STREET NAME	SEW	DW	NDW	GAS	COMS	ELEC	POLES	вок
BONANG ROAD	-	3.15 E	2.675 E	2.25 E	1.775 W	2.20 W	*0.80 W	3.95 W/4.25
BREEZY CCT. LOT 3323	1.00 W	2.90 E	2.50 E	2.10 E	1.775 W	2.20 W	*0.80 W	4.35
BREEZY CCT. LOT 3328-3331	-	2.90 E	2.50 E	2.10 E	1.775 W	2.20 W	*0.80 W	4.35
BREEZY CCT. LOT 3350	-	2.90 W	2.50 W	2.10 W	2.275 E	2.70 E	*0.80 E	4.35 W/ 4.85
DISTRICT AVENUE	1.00 E	3.15 W	2.675 W	2.25 W	1.775 E	2.60 E	*0.80 E	4.35
GOKULA ST. LOT 3345	1.00 E	2.90 W	2.50 W	2.10 W	1.775 E	2.20 E	*0.80 E	4.35
MOYNE ROAD	1.00 W	3.15 E	2.675 E	2.25 E	1.775 W	2.20 W	*0.80 W	3.95 W/4.25
PRANA WAY	-	2.90 S	2.50 S	2.10 S	1.775 N	2.20 N	*0.80 N	4.35
RAWSON CIRCUIT	1.00 W	2.95 E	2.50 E	2.10 E	1.775 W	2.20 W	*0.80 W	4.35
TULSI AVE. LOTS 3304-3307, 3312-3315	1.00 N/S	3.40 N	2.70 N	2.10 N	1.775 S	2.20 S	*0.80 S	6.30
TULSI AVE. LOTS 3316-3317	-	3.40 N	2.70 N	2.10 N	1.775 S	2.20 S	*0.80 S	6.30

* FROM BACK OF KERB

NOTE: PARKING BAYS

WHERE APPLICABLE PARKING BAYS TO NEATLY MATCH AND TRANSITION INTO CROSSOVERS AS NOMINATED ON DP01-DP03. ALL OTHER PARKING BAYS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH TD02.

TBM SCHEDULE

I.D.	TYPE	EASTING	NORTHING	LEVEL
243	ROD	292970.124	5800172.240	16.17
247	PM 32	293136.811	5800075.951	22.20
6002	ROD	293152.965	5800132.136	19.94

TBM'S No. 6002 & 247 ARE SHOWN IN DRG. No. 10933SP01, SHEET No. 05.

NOTE: EXISTING SURFACE LEVELS

ALL EXISTING SURFACE LEVELS SHOWN ON THIS PLAN ARE PRIOR TO THE COMMENCEMENT OF PERMIT 6 BULK EARTHWORKS (DCE JOB NUMBER 10868).

NOTE: END OF PAVEMENT WORKS

CONCRETE EDGE STRIP AND AG DRAIN TO BE INSTALLED TO THE END OF ALL PAVEMENT WORKS.

NOTE: EXISTING SERVICES

ALL EXISTING SERVICES UNDER NEW AND PROPOSED ROAD PAVEMENT, FOOTPATH AND DRIVEWAYS TO BE FCR BACKFILLED.

NOTE: EXISTING STRUCTURES

ALL EXISTING DRAINAGE PITS AND SEWER STURCTURES WITHIN NEW WORKS ARE TO BE ADJUSTED TO MATCH NEW FINISHED SURFACE LEVELS.

NOTE: TACTILE PAVING

TACTILE GROUND SURFACE INDICATORS (TGSI'S) ARE SHOWN INDICATIVELY AND SHOULD BE CONSTRUCTED IN ACCORDANCE WITH AS/NZS 1428.4.1:2009.

BEWARE!

DEVELOPMENT VICTORIA FTTH OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 03 9311 4575.

BEWARE!

NBN OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 1800 687 626.

BEWARE!

TELSTRA OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 9253 8263.

CAUTION!

TELSTRA MAJOR CABLES ARE IN THE VICINITY OF WORKS.

DANGER!

OVERHEAD ELECTRICITY TRANSMISSION LINES. CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN OPERATING IN THE VICINITY OF THESE LINES. THE CONTRACTOR MUST ADHERE TO ALL "NO GO ZONE" REQUIREMENTS OF THE POWER AUTHORITY.

WARNING!


NO DRAINAGE WORKS SHALL COMMENCE UNTIL THE CONTRACTOR CONFIRMS THE I.L. OF ALL EXISTING DRAINS, AND CONFIRMS IN WRITING WITH THE ENGINEERING SUPERVISOR.

WARNING!

THE LOCATION OF EXISTING SERVICES SHOWN ON THESE PLANS MUST BE PROVEN ON SITE, THE APPROPRIATE AUTHORITY MUST BE CONTACTED AND THE SERVICES LOCATED PRIOR TO COMMENCEMENT OF ANY WORKS.

WARNING!

BEWARE OF ASBESTOS! SOME UNDERGROUND SERVICES MAY BE CONSTRUCTED FROM ASBESTOS CONTAINING MATERIAL. CONTACT THE SUPERINTENDENT FOR INSTRUCTIONS ON HOW TO MANAGE ANY POTENTIAL ASBESTOS HAZARD.



Scale @ A1/A3

1:500 / 1:1000

CONCRETE PARKING BAY

RIVERWALK STAGE 33 **GEELONG ROAD, WERRIBEE** WYNDHAM CITY COUNCIL **DETAIL PLAN SHEET 02 OF 03** Drawing No. 10933DP02

Sheet No. 07 of 52

VICTORIA T61398137400 W dceng.com.au

Rev 0

CONSULTING ABN 78 429 221 049 QUEENSLAND T 61 7 3374 9000

E info@dceng.com.au


CONSTRUCTION

LOTS 3302 TO 3303 AND 3318 TO 3323 SCALE @ A1/A3 1:250/1:500

TABLE OF SERVICE LOCATIONS

STREET NAME	SEW	DW	NDW	GAS	COMS	ELEC	POLES	BOK
BONANG ROAD	-	3.15 E	2.675 E	2.25 E	1.775 W	2.20 W	*0.80 W	3.95 W/4.25 E
BREEZY CCT. LOT 3323	1.00 W	2.90 E	2.50 E	2.10 E	1.775 W	2.20 W	*0.80 W	4.35
BREEZY CCT. LOT 3328-3331	-	2.90 E	2.50 E	2.10 E	1.775 W	2.20 W	*0.80 W	4.35
BREEZY CCT. LOT 3350	-	2.90 W	2.50 W	2.10 W	2.275 E	2.70 E	*0.80 E	4.35 W/ 4.85 E
DISTRICT AVENUE	1.00 E	3.15 W	2.675 W	2.25 W	1.775 E	2.60 E	*0.80 E	4.35
GOKULA ST. LOT 3345	1.00 E	2.90 W	2.50 W	2.10 W	1.775 E	2.20 E	*0.80 E	4.35
MOYNE ROAD	1.00 W	3.15 E	2.675 E	2.25 E	1.775 W	2.20 W	*0.80 W	3.95 W/4.25 E
PRANA WAY	-	2.90 S	2.50 S	2.10 S	1.775 N	2.20 N	*0.80 N	4.35
RAWSON CIRCUIT	1.00 W	2.95 E	2.50 E	2.10 E	1.775 W	2.20 W	*0.80 W	4.35
TULSI AVE. LOTS 3304-3307, 3312-3315	1.00 N/S	3.40 N	2.70 N	2.10 N	1.775 S	2.20 S	*0.80 S	6.30
TULSI AVE. LOTS 3316-3317	_	3.40 N	2.70 N	2.10 N	1.775 S	2.20 S	*0.80 S	6.30

* FROM BACK OF KERB



INSET B LOTS 3345 TO 3350 SCALE @ A1/A3 1:250/1:500

TBM SCHEDULE

1.1	٥.	TYPE	EASTING	NORTHING	LEVEL
24	+3	ROD	292970.124	5800172.240	16.17
24	٠7	PM 32	293136.811	5800075.951	22.20
60	02	ROD	293152.965	5800132,136	19.94

NOTE: PARKING BAYS

EARTHWORKS (DCE JOB NUMBER 10868).

THE END OF ALL PAVEMENT WORKS.

WHERE APPLICABLE PARKING BAYS TO NEATLY MATCH AND TRANSITION INTO CROSSOVERS AS NOMINATED ON DP01-DP03. ALL OTHER PARKING BAYS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH TD02.

BACKFILLED.

TBM'S No. 6002 & 247 ARE SHOWN IN DRG. No. 10933SP01, SHEET No. 05.

NOTE: EXISTING SURFACE LEVELS ALL EXISTING SURFACE LEVELS SHOWN ON THIS PLAN ARE PRIOR TO THE COMMENCEMENT OF PERMIT 6 BULK

NOTE: END OF PAVEMENT WORKS CONCRETE EDGE STRIP AND AG DRAIN TO BE INSTALLED TO

NOTE: EXISTING SERVICES ALL EXISTING SERVICES UNDER NEW AND PROPOSED ROAD PAVEMENT, FOOTPATH AND DRIVEWAYS TO BE FCR

NOTE: EXISTING STRUCTURES ALL EXISTING DRAINAGE PITS AND SEWER STURCTURES

WITHIN NEW WORKS ARE TO BE ADJUSTED TO MATCH NEW

NOTE: TACTILE PAVING

FINISHED SURFACE LEVELS.

TACTILE GROUND SURFACE INDICATORS (TGSI'S) ARE SHOWN INDICATIVELY AND SHOULD BE CONSTRUCTED IN ACCORDANCE WITH AS/NZS 1428.4.1:2009.

Scale @ A1/A3

BEWARE!

NBN OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 1800 687 626.

BEWARE!

TELSTRA OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 9253 8263.

WARNING!

THE LOCATION OF EXISTING SERVICES SHOWN ON THESE PLANS MUST BE PROVEN ON SITE, THE APPROPRIATE AUTHORITY MUST BE CONTACTED AND THE SERVICES LOCATED PRIOR TO COMMENCEMENT OF ANY WORKS.

DANGER!

OVERHEAD ELECTRICITY TRANSMISSION LINES. CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN OPERATING IN THE VICINITY OF THESE LINES. THE CONTRACTOR MUST ADHERE TO ALL "NO GO ZONE" REQUIREMENTS OF THE POWER AUTHORITY.

CAUTION!

TELSTRA MAJOR CABLES ARE IN THE VICINITY OF WORKS.

BEWARE!


DEVELOPMENT VICTORIA FTTH OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 03 9311 4575.

WARNING!

NO DRAINAGE WORKS SHALL COMMENCE UNTIL THE CONTRACTOR CONFIRMS THE I.L. OF ALL EXISTING DRAINS, AND CONFIRMS IN WRITING WITH THE ENGINEERING SUPERVISOR.

WARNING!


BEWARE OF ASBESTOS! SOME UNDERGROUND SERVICES MAY BE CONSTRUCTED FROM ASBESTOS CONTAINING MATERIAL. CONTACT THE SUPERINTENDENT FOR INSTRUCTIONS ON HOW TO MANAGE ANY POTENTIAL ASBESTOS HAZARD.





Written dimensions to take precedence over scale. Contractor shall check and verify all dimensions on site. Discrepancies to be brought to the attention of the Superintendent.




© Dalton Consulting Engineers Pty Ltd













RIVERWALK

1:250 / 1:500

STAGE 33 GEELONG ROAD, WERRIBEE WYNDHAM CITY COUNCIL **DETAIL PLAN SHEET 03 OF 03** Drawing No. 10933DP03

Sheet No. 08 of 52

VICTORIA T61398137400 W dceng.com.au

Rev 0

CONSULTING ABN 78 429 221 049 QUEENSLAND T 61 7 3374 9000 E info@dceng.com.au

CONSTRUCTION