



**Planning and Environment Act 1987**  
**Wyndham Planning Scheme**

**Approved Plan As Required**  
**under Condition 31**  
**Permit No WYP11630/19**  
**Date 14/05/2022**

**TBM SCHEDULE**

I.D.	TYPE	EASTING	NORTHING	LEVEL
239	SPIKE	292356.277	5799865.167	15.08
543	RIVET	292507.335	5800157.434	16.39
6005	ROD	292413.270	5799771.124	14.93

REV	DESCRIPTION	DATE	AMEND	APP'D
0	CONSTRUCTION ISSUE	02/05/22	SR/JB	TL

Drawn M.MATHER  
 Date 24/03/21  
 AN 3131094  
 Designed S.RAJKOVIC  
 Date 12/01/21  
 AN 2951026  
 Checked J.HOLLAND  
 Date 25/01/21  
 AN 972434  
 Approved T.LIAKOPOULOS  
 Date 02/05/22  
 AN 889351

**LEGEND**

- STAGE BOUNDARY
- DETAIL PLAN BOUNDARY
- CURRENT STAGE



**RIVERWALK**  
**STAGE 34**  
**GEELONG ROAD, WERRIBEE**  
**WYNDHAM CITY COUNCIL**  
**STAGING PLAN**

**DALTON CONSULTING ENGINEERS**  
 ABN 78 429 221 049  
 VICTORIA T 61 3 9813 7400 W dceng.com.au  
 QUEENSLAND T 61 7 3374 9000 E info@dceng.com.au

**CONSTRUCTION**

Drawing No. 10934SP01 Rev 0  
 Sheet No. 03 of 38

Drawing File: C:\124\_Synergy\werra\ENERGY-ME\10934-Riverwalk - Stage 34\_1767\1\_DESIGN\01\_A040\04\_001.dwg  
 Date/Time: Mon May 02, 2022 3:42pm  
 User: jrb

Written dimensions to take precedence over scale. Contractor shall check and verify all dimensions on site. Discrepancies to be brought to the attention of the Superintendent.  
 © Dalton Consulting Engineers Pty Ltd

STAGE 32  
(EXISTING CONSTRUCTION)

TBM SCHEDULE

I.D.	TYPE	EASTING	NORTHING	LEVEL
239	SPIKE	292356.277	5799865.167	15.08
543	RIVET	292507.335	5800157.434	16.39
6005	ROD	292413.270	57999771.124	14.93

NOTE: TBM'S  
TBMS SHOWN IN THE TABLE ABOVE ARE OUTSIDE OF VIEWPORT SHOWN. REFER TO 10934SP01 FOR LOCATION OF TBMS IN RELATION TO STAGE 34 WORKS.

NOTE: EXISTING SURFACE LEVELS  
ALL EXISTING SURFACE LEVELS SHOWN ON THIS PLAN ARE PRIOR TO THE COMMENCEMENT OF PERMIT 6 BULK EARTHWORKS (DCE JOB NUMBER 10668).

NOTE: END OF PAVEMENT WORKS  
CONCRETE EDGE STRIP AND AG DRAIN TO BE INSTALLED TO THE END OF ALL PAVEMENT WORKS.

NOTE: EXISTING SERVICES  
ALL EXISTING SERVICES UNDER NEW AND PROPOSED ROAD PAVEMENT, FOOTPATH AND DRIVEWAYS TO BE FCR BACKFILLED.

NOTE: EXISTING STRUCTURES  
ALL EXISTING DRAINAGE PITS AND SEWER STRUCTURES WITHIN NEW WORKS ARE TO BE ADJUSTED TO MATCH NEW FINISHED SURFACE LEVELS.

NOTE: TACTILE PAVING  
TACTILE GROUND SURFACE INDICATORS (TGS/SGI) ARE SHOWN INDICATIVELY AND SHOULD BE CONSTRUCTED IN ACCORDANCE WITH AS/NZS 1428.4:12009.

**BWARE!**  
DEVELOPMENT VICTORIA FTTH OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 03 9311 4575.

**BWARE!**  
NBN OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 1800 687 626.

**BWARE!**  
TELSTRA OPTIC FIBRE CABLES IN THE VICINITY OF WORKS. TEL: 9253 8263.

**CAUTION!**  
TELSTRA MAJOR CABLES ARE IN THE VICINITY OF WORKS.

**DANGER!**  
OVERHEAD ELECTRICITY TRANSMISSION LINES. CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN OPERATING IN THE VICINITY OF THESE LINES. THE CONTRACTOR MUST ADHERE TO ALL "NO GO ZONE" REQUIREMENTS OF THE POWER AUTHORITY.

**WARNING!**  
NO DRAINAGE WORKS SHALL COMMENCE UNTIL THE CONTRACTOR CONFIRMS THE I.L. OF ALL EXISTING DRAINS, AND CONFIRMS IN WRITING WITH THE ENGINEERING SUPERVISOR.

**WARNING!**  
THE LOCATION OF EXISTING SERVICES SHOWN ON THESE PLANS MUST BE PROVEN ON SITE, THE APPROPRIATE AUTHORITY MUST BE CONTACTED AND THE SERVICES LOCATED PRIOR TO COMMENCEMENT OF ANY WORKS.

**WARNING!**  
**BWARE OF ASBESTOS!**  
SOME UNDERGROUND SERVICES MAY BE CONSTRUCTED FROM ASBESTOS CONTAINING MATERIAL. CONTACT THE SUPERINTENDENT FOR INSTRUCTIONS ON HOW TO MANAGE ANY POTENTIAL ASBESTOS HAZARD.



TABLE OF SERVICE LOCATIONS

STREET NAME	SEW	DW	NDW	GAS	COMS	ELEC	POLES	BOK
KALYANI STREET	-	2.90 W	2.50 W	2.10 W	1.775 E	2.20 E	+0.80 E	4.35
SHANTI CCT.	LOT 3401, 3404-3403	1.20 N	3.60 N	3.15 N	2.75 N	-	-	4.85 N/2.35 S
SHANTI CCT.	LOT 3403-3402	-	2.95 W	2.50 W	2.10 W	1.775 E	2.20 E	+0.80 E
RAWSON CCT.	LOT 3459-3467	1.00 E/W	2.90 W	2.50 W	2.10 W	1.775 E	2.20 E	+0.80 E
RAWSON CCT.	LOT 3468	-	-	3.60 N	3.15 N	2.75 N	-	4.85 N/2.35 S
SHARED PATH A	-	1.60 N	4.25 N	3.75 N	3.25 N	-	-	-

\* FROM BACK OF KERB

REV	DESCRIPTION	DATE	AMEND	APPD
0	CONSTRUCTION ISSUE	02/05/22	SR/JB	TL

Drawn M.MATHER  
Date 24/03/21  
AN 3131094  
Designed S.RAJKOVIC  
Date 12/01/21  
AN 2951026  
Checked J.HOLLAND  
Date 25/01/21  
AN 972434  
Approved T.LIAKOPOULOS  
Date 02/05/22  
AN 889351  
Dalton Consulting Engineers Pty Ltd

LEGEND

- EX W - EX. WATER MAIN
- EX G - EX. GAS MAIN
- EX E - EX. ELECTRICAL CABLE
- EX S - EX. SEWER MAIN & MH
- EX T - EX. COMM. CABLE & PIT
- EX D - EX. DRAIN & PIT
- E — ELECTRICITY
- T — TELECOMMUNICATIONS
- G — GAS
- GC — GAS CONDUIT
- W — WATER
- WC — WATER CONDUIT
- RW — RECYCLED WATER
- RCW — REC. WATER CONDUIT
- S — SEWER MAIN & MANHOLE
- SW — SW DRAIN & PIT
- H — HOUSE DRN | PROP. INLET
- FS21.650 — FINISHED SURFACE LEVEL
- ES20.06 — EX. SURFACE LEVEL
- R — REGRADE LOT AT MIN 1 IN 150
- O — OVERLAND FLOW
- F — FILLING OVER 200mm
- A — ASPHALT PAVEMENT
- C — CONCRETE PATH | D'WAY
- SH — CONCRETE SHARED PATH
- T — EX. TREE TO REMAIN
- FA — FUTURE ACOUSTIC WALL
- L — LIMIT OF WORKS
- PSM | TBM

DEVELOPMENT VICTORIA

Scale @ A1/A3 1:500 / 1:1000

Coords: MGA Levels: AHD

**DIAL BEFORE YOU DIG**  
www.1100.com.au

RIVERWALK  
STAGE 34  
GEELONG ROAD, WERRIBEE  
WYNDHAM CITY COUNCIL  
DETAIL PLAN

Drawing No. 10934DP01  
Sheet No. 04 of 38

DALTON CONSULTING ENGINEERS  
ABN 78 429 221 049  
QUEENSLAND  
T 61 7 3374 9000  
E info@dceng.com.au

VICTORIA  
T 61 3 9813 7400  
W dceng.com.au

**CONSTRUCTION**

Drawing File: C:\12d\_Synergy\delta\delta\ENERGY-ME\10934-Riverwalk - Stage 34\_17671 - DESIGN\01\_ACAD\04\_08  
 10934DP01.dwg - (P01)  
 Date/Time: Mon May 02, 2022 - 3:42pm - jph